

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Beach
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1971
CONSERVATION DIVISION
Wichita, Kansas
12-15-71

Operator's Full Name Chief Drilling Company, Incorporated,
 Complete Address 905 Century Plaza, Wichita, Kansas.
 Lease Name Porter Well No. 1
 Location CSW-NE Sec. 3 Twp. 14 Rge. (E) (W) 27
 County Cove Total Depth 2229'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Above
 Address License No.
 Operation Completed: Hour 11:30 PM Day 13 Month 12 Year 1971

The above well was plugged as follows:

267'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru
DP from 280' to 205'. Pulled DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols

Well Plugging Supervisor

DATE 12/15/71INV. NO. 4819-W