

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1962
08-31-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mayfield & Smith

Complete Address: 227 Union Center Wichita, Kansas

Lease Name Leonhardt Well No. 1

Location SE SE SE Sec. 20 Twp. 14 Rge. (E) (W) 18

County Ellis Total Depth 3791

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Kent Well Service

Address: El Dorado, Kansas License No. 394

Operation Completed: Hour 7:30PM Day 29 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 177' circulated with cement - 5 1/2" 3749', with 150 sax cement.
Perf 3417' - run tools in hole and found bridge at 3640'.

Set plugs and sanded back to 3380', set 4 sax cement with dump bailer -
pulled 2200' 5 1/2" to 450', circulated hole with heavy mud - displaced
20 sax cement through 5 1/2" - heavy mud to 180' - displaced 20 sax cement
through 5 1/2" - heavy mud to 40', set plug, sand and 10 sax cement to bottom
cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 8/31/62
INV. NO. 3622-u

Signed: [Signature]
Well Plugging Supervisor