

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 05L- 21,601 -00-00 (of this well)

Operator's Full Name Nielson Enterprises, Inc.

Complete Address 633 17th St., Suite 1380, Denver, Colorado

Lease Name Rohr Well No. 1

Location 660' FWL & 550' FSL of NW/4 <sup>110.5 csg SW NW</sup> Sec. 20 Twp. 14 Rge. (E) (W) 18

County Ellis Total Depth 3720'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 3 A Day 4 Month 12 Year 1978

The above well was plugged as follows:

RTD 3720' 8 5/8 csg set 234' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 5 1978  
12-05-78  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. Massey  
Well Plugging Supervisor

12-6-78  
8663-W