

15-051-30408-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

DEC 21 1966

12.21.66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Marshall Nye

Complete Address: 620 Cravens Bldg. Oklahoma City, Okla.,

Lease Name Befort Well No. 1

Location NE SW 1/4 990' FSL & 990' FWL of SW 1/4 Sec. 19 Twp. 14 Rge. 18 (E) (W) X

County Ellis Total Depth 3775'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Braden Drilling Co.,

Address: Wichita, Kansas License No.

Operation Completed: Hour 12 P Day 18 Month 12 Year 1966

The Above well was plugged as follows:

RTD 3775' 8 5/8 csg set at 243' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc
cement thru drill pipe. Heavy mud to 230' set cementing plug and displaced 20 sc cem.
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to
base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Marsing
Well Plugging SupervisorDATE 12/21/66
INV. NO. 4503-W