

15-051-00591-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NE

SEC. 15 TWP. 14 RGE. 18

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Board of Regents "B"

Operator Petroleum Inc Address 311 ^{Rt. 2} Wichita, Kans Ct. Bend, Ks.

Field _____ County Ellis

Total Depth 3660 Feet.

Plugging Contractor Garvey Drng Co & Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1215' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 600', displaced 40 sax cement through drill pipe, heavy mud to 240', set cementing plug and displaced 40 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Cementing by Globe Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION
11-26-57
NOV 26 1957

Edwin Kelly
District Conservation Agent

Date 11-23-57

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC 15, T 14, R 18W
BOOK PAGE 64 LINE 2