

15-051-19474-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NE

SEC. 15 TWP. 14 RGE. 18

lost hole
Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-1 Lease Board of Regents

Operator Petroleum Inc Address Wichita, Kans

Field _____ County Ellis

Total Depth 1214 Feet.

Plugging Contractor Garvey Drg Co & Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" hit bridge at 1092' - lost 204' in hole.

Gunned bits, filled hole with heavy mud, displaced 75 sax through

drill pipe at 655' (50% cement, 50% Stratocrete, 2% Calcium), heavy

mud to 250', circulated hole from 250' to 0' through drill pipe

with 255 sax (50% cement, 50% stratocrete and 2% calcium chloride.)

Cementing by Globe Cementing Co.

Edson Petty
District Conservation Agent

Date 11-15-57

11-18-57

