

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Associated Petroleum Co.

Complete Address 4th Floor Petroleum Bldg., Tulsa, Oklahoma

Lease Name Daniel M. Pfeifer Well No. 1

Location NW NE NW Sec. 7 Twp. 14 Rge. (E) (W) 18

County Ellis Total Depth 3750

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Sage Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 9:15P Day 20 Month 4 Year 1970

The above well was plugged as follows:

RTD 3750' 8 5/8 csg set at 248' cwc Cmt. Mat. 50-50 poz cmt W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 4/23/70
INV. NO. 1582-W