

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22597 0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Rupe Oil Company, Inc.

Complete Address P. O. Box 2273, Wichita, Kansas 67201

Lease Name Fort Hays State Well No. #1

Location NW/NE/NE Sec. 7 Twp. 14 Rge. 18 (East) (West)

County Ellis Total Depth 3750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kandrilco, L.T.D.

Address 555 N. Woodlawn Bldg, Suite #207, License No. _____
Wichita, Kansas 67202

Operation Completed: Hour: 11:00AM. Day: 22nd Month: Oct. Year: 19 81

Plugging Operations attended by Agent? All Part _____ None _____

The above well was plugged as follows:

8 5/8"-236' s.p. cuc. w/175 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement.

5 sacks of cement in rat hole and 5 sacks of cement in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1981

I hereby certify that the above well was plugged as herein stated.

DATE 11-24-81

INV. NO. 8468-W

Signed: _____

Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas