


15-109-20001-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Associated Petroleum Company,

Complete Address: Fourth Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name R. H. Steele Trustees Well No. 1-A

Location NW-SW-SE Sec. 15 Twp. 14 Rge. (E) (W) 32

County Logan Total Depth 4965

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. _____

Operation Completed: Hour 3:00 P Day 6 Month 5 Year 1968

The Above well was plugged as follows:

152'--8 5/8" Surface pipe, cement circulated.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 100 Sx. cement thru
DP from 825' to 500'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 5/10/68

INV. NO. 7928-41