



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Oller of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Brungson- Spines

Complete Address: 800 Wichita Plaza Wichita, Kansas

Lease Name: Brungardt Well No. 1

Location: SE SE Sec. 13 Twp. 14 Rge. 16 (E)(W) XX

County: Ellis Total Depth 3500' Oil Well

Gas Well Input Well SWD Well D & AX Lost Hole

Mr. Oller was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 500' and displace
50 sc cement thru drill pipe. Heavy mud to 200' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

OCT 14 1968

CONSERVATION DIVISION

Wichita, Kansas

10-14-1968

Don F. Muesel
Conservation Division Agent