



15-063-20021-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: R. Long Well No. 1

Location: CNE-NW Sec. 15 Twp. 14 Rge. (E)(W) 27

County: Gove Total Depth 4405' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

272'--8 5/8" Surface casing, cement circulated.
4405'--5 1/2" Production casing, cemented on bottom with 135 Sx. No plug back indicated. Top perforations @ 4300'.

Sand well back to 4250' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx. cement staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent