



15-063-20022-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: R. Long Well No. 2

Location: NW-NW Sec. 15 Twp. 14 Rge. (E)(W) 27

County: Gove Total Depth 4415' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

273'--8 5/8" Surface casing, cement circulated with 235 Sx.
4415'--5 1/2" Production casing cemented on bottom with 75 Sx. Well
plugged back to 4328'. Top perforation @ 4302'.

Sand well back to 4275' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx.
cement, staged.

Very truly yours,

R. L. Nichols
Conservation Division Agent