

State of Kansas



15-063-20610-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
AUG 10 1967  
08-10-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jim Smith of Tidewater Oil Company, has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Tidewater Oil Company

Complete Address: Box #752, Drumright, Oklahoma

Lease Name: Frank Rhoades Well No. 2

Location: 1980' SNL & 660' EWL Sec. 14 Twp. 14 Rge. (E)(W) 27

County Gove Total Depth 4421' Oil Well         

Gas Well          Input Well          SWD Well          D & A           Lost Hole         

Mr. Smith was instructed to plug the well as follows:

270' -- 8 5/8" Surface pipe, cement circulated with 200 Sx. Dakota section from 1420' to 1600'.

Circulate hole with heavy mud. Pull DP. to 1670' and displace 110 Sx. cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent