



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clemith Burton of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Rhoades Well No. A-1

Location: CNE-NW Sec. 11 Twp. 11 Rge. (E)(W) 27

County: Gove Total Depth 1327' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 115 Sx.  
top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 925' and displace 125 Sx.  
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.  
Full DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Dinkel  
Conservation Division Agent