

State of Kansas



15-063-20096-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Lindenmuth of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated.

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Porter Well No. 1

Location: CSW-NE Sec. 3 Twp. 14 Rge. (E)(W) 27

County: Gove Total Depth 2229' Oil Well _____

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

267'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. G. Dickole

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1971
CONSERVATION DIVISION
WICHITA, KANSAS