

State of Kansas



15-051-21334 00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 05 1977
07-05-1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Cotton of H-30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cotton guarantees payment of the plugging fee.

Operator's full Name: Euwer Petroleum Co. & Parrish Oil Co.

Complete Address: 110 N. Market, Suite 206, Litwin Bldg., Wichita, Ks.

Lease Name: Schumacher Well No. 1

Location: SW NW SW Sec. 23 Twp. 14 Rge. (E)(W) 17

County: Ellis Total Depth 3550' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cotton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 185' set 25 sk cmt plug thru drill pipe Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent