


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec 27 Twp. 14S Rge. (E) 18 (W)
Location as "NE/CNWxSWx" or footage from lines 10' W of C SE SW SW
Lease Owner Clinton Oil Company
Lease Name Mary Engle Well No. 2-D
Office Address 217 N. Water, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 21 1969
Application for plugging filed Verbal Approval
Application for plugging approved Verbal Approval
Plugging commenced August 21 1969
Plugging completed August 21 1969
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 285' | None |
| RECEIVED STATE CORPORATION COMMISSION AUG 29 1969 CONSERVATION DIVISION Wichita, Kansas | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,677 feet (rotary total depth) to 500 feet. Set plug at 500 feet and cemented with 70 sacks cement. Filled hole with heavy rotary mud to 270 feet. Set plug at 270 feet and cemented with 20 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented to cellar with 10 sacks cement, 2 sacks cement in rat hole. All cementing done by Sun Oilwell Cementing Co. pump truck.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of August, 1969

My commission expires _____
Notary Public
Martha Hartpence
Notary Public.

15-051-20482-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Clinton Oil Company

SEC. 27 T. 14S R. 18W
LOC. 10' W of C SE SW SW


FARM Mary Engel NO. 2-D

TOTAL DEPTH 3,677'
COMM. August 11, 1969
SHOT OR TREATED
CONTRACTOR H-30, INC.
ISSUED

COMP. August 21, 1969

COUNTY Ellis

KANSAS



CASING

| | | | |
|----|--------|-------------------------------|-------------------|
| 20 | 10 | | |
| 15 | 8-5/8" | 285' cemented w/175 sx cement | ELEVATION 2064 KB |
| 12 | 6 | | |
| 13 | 5 | | |

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

ELECTRIC LOG TOPS

| | | | | |
|----------------------|------|--------------|------|-------|
| Surface Clay | 85 | Anhydrite | 1242 | + 822 |
| Shale | 286 | Topeka | 3012 | - 948 |
| Surface Clay & Shale | 440 | Heebner | 3288 | -1224 |
| Shale | 690 | Toronto | 3308 | -1244 |
| Sand | 895 | Lansing | 3334 | -1270 |
| Red Bed | 1239 | Conglomerate | 3646 | -1582 |
| Anhydrite | 1280 | Arbuckle | 3667 | -1603 |
| Shale | 1625 | Log T.D. | 3675 | -1611 |
| Shale & Salt | 1850 | Rotary T.D. | 3677 | -1613 |
| Lime Streaks & Shale | 2000 | | | |
| Shale & Lime | 2244 | | | |
| Lime & Shale | 2530 | | | |
| Shale & Lime | 2990 | | | |
| Lime & Shale | 3020 | | | |
| Lime | 3652 | | | |
| Shale & Lime | 3677 | | | |
| Rotary Total Depth | 3677 | | | |

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1969
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th day of August, 1969.

Martha Hartpence
Martha Hartpence-Notary Public

My Commission Expires:

April 21, 1971