

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 27 TWP. 14S RGE. 18 NE/W  
Location as in quarters or footage from lines:  
SE, SE, NW, Sec. 27, 2310' from N. Line & 2310' from W. Line


Lease Owner Coastal Oil & Gas Corporation  
Lease Name Schumacher Well No. 4  
Office Address Box 1332 Amarillo, Texas 79189  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 4-6-84  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 4-6-84  
Plugging completed 4-6-84  
Reason for abandonment of well or producing formation \_\_\_\_\_

(CL)

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation -- Depth to top -- bottom -- T.D. 3760'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

- Plug #1 3630'-3541' w/20 sx 50-50 poz. 6% gel, 3% CaCl<sub>2</sub>, 3.2/sx flocele
- Plug #2 1300'-1211' w/20 sx 50-50 poz, 6% gel, 3% CaCl<sub>2</sub>, 3.2/sx flocele
- Plug #3 600'-148' w/100 sx, set 1 sx cotton seed hulls, set wooden plug @ 40'
- Plug #4 40'-Surface w/10 sx cement, RH w/10 sx cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Ellis, ss.

James E. Adams (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) James E. Adams  
Box 1332 Amarillo, Texas 79189  
(Address)

RECEIVED  
APR 27 1984  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN before me this 25 day of April, 1984

M. R. [Signature]  
Notary Public.

My Commission expires: 11-12-85

# WELL LOG

COMPANY COASTAL OIL & GAS CORPORATION  
 600 17th St., Suite 800 S. Tower  
 Denver, CO 80201-0749


FARM SCHUMACHER NO. 4

SEC. 27 T. 14S R. 18W  
 LOC. 2310' FNL & 2310' FWL

RID. NO. 15  
 TOTAL DEPTH 3760'  
 COMM. 3-29-84 COMP. 4-6-84

COUNTY Ellis  
 KANSAS

CONTRACTOR MURFIN DRILLING COMPANY  
 250 N. Water, Suite 300  
 Wichita, KS 67202



CASING

20	10	
15	8-5/8" csg set @ 433' w/250 sx Class A,	ELEVATION
12	6 2% gel, 3% cc	
13	5	PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil & Sand	432'
Sand & Shale	1360'
Anhydrite	1294'
Shale & Sand	1597'
Shale	2565'
Shale & Lime (RTD)	3760'

RECEIVED  
 STATE CORPORATION COMMISSION


MAY 17 1984

CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas  
 County of Sedgwick } ss:

I, David L. Murfin of the Murfin Drilling Company

upon oath depose that the above and foregoing is a true and correct copy of the log of the Schumacher #4 well.



*David L. Murfin*  
 David L. Murfin

Subscribed and sworn to before me this 10th day of April 19 84

My Commission Expires 4-25-87

*Eleanor Hall*  
 Eleanor Hall NOTARY PUBLIC