


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis

County. Sec. 27 Twp. 14S Rge. (X) 18(W)

Location as "NE/CNW&SW4" or footage from lines. SW NE NE
Lease Owner. Raymond Oil Company, Inc.
Lease Name. Pfeifer Well No. 1
Office Address. 410 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. January 30 19 67
Application for plugging filed. February 8 19 67
Application for plugging approved. February 1 19 67
Plugging commenced. January 30 19 67
Plugging completed. January 30 19 67
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	274'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Plug at 600' w/25 sx cement; Plug #2 at 260' - 1/4 sx hulls and 20 sx cement; Plug #3 at 40' with 1/2 sx hulls and 8 sx cement.

RECEIVED
FEB 10 1967
02-10-67
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor. Raymond Oil Company, Inc.
Address. 410 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wm. M. Raymond (employer or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm M Raymond
410 Fourth National Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 67

My commission expires February 15, 1967

Ronnie Donnelly
Notary Public

RAYMOND OIL COMPANY, INC.
 #1 PFEIFER
 SW NE NE Sec. 27-14S-18W
 Ellis County, Kansas

ELEVATION: 2013 KB
 2011 DF (L&S)
 2008 GL

Drilling Contractor: Company Tools
 Date Commenced: January 26, 1967
 Date Completed: January 30, 1967

Casing Record
 8-5/8" @ 274' w/200 sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Shale & Clay	274
Blue Shale	375
Red Shale	460
Shale	630
Red Bed & Shale	1216
Lime & Shale	1260
Shale & Shells	1631
Shale	1855
Shale & Lime	2157
Lime	2277
Lime & Shale	2463
Shale & Lime	2605
Lime w/Shale Streaks	2745
Lime & Shale	2887
RTD	2887

RECEIVED
 STATE OF KANSAS
 FEB 10 1967
 CONSERVATION DIVISION
 TOPEKA, KANSAS

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm M Raymond
 Wm. M. Raymond

SUBSCRIBED and sworn to before me, this 9th day of February, 1967.

Ronnie Donnelly
 Ronnie Donnelly - Notary Public

My commission expires:

February 15, 1967