

15-051-01512-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Ellis County, Sec. 24 Twp. 14S Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Don E. Pratt
Lease Name E. Leiker Well No. 1
Office Address Box 656, Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed Oct. 28 19 64
Application for plugging filed Oct. 28 19 64
Application for plugging approved Oct. 28 19 64
Plugging commenced Oct. 28 19 64
Plugging completed Oct. 28 19 64
Reason for abandonment of well or producing formation D & A
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3590 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1150'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug 1/2 sx hulls @ 300'
cemented with 35 sx. Left
top plug out for farmer water
well.

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1964

11-13-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of October, 19 64

My commission expires 5-22-66 Notary Public.

DRILLERS LOG

E. Leiker No. 1

CASING RECORD: 8 5/8" @ 1150'
w/550 sx cement

COMPANY: Don E. Pratt

CONTRACTOR: Red Tiger Drilling Co. NE NE SW
24-14S018W

COMMENCED: October 19, 1964 Ellis County, Kans.

COMPLETED: October 28, 1964

ELEVATION: 1953 DF
1956 RB

TOTAL DEPTH: 3590'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Cellar Shale	0	40	
Sandy Shale Pyrite	40	93	
Shale & Shells	93	235	
Shale Shells & Clay	235	520	
Sand	520	792	
Redbed	792	1138	
Anhydrite	1138	1185	
Redbed Shale & Shells	1185	1820	
Shale & Lime	1820	3035	
Lime	3035	3100	
Lime & Shale	3100	3247	
Lime	3247	3485	
Conglomerate	3485	3551	
Lime	3551	3590	

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1964

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log
to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 30th day of October, 1964.

Jean Shellen
Notary Public

My Commission Expires:

5-22-66