

15-051-22395-00-00

Form CP-4  
Rev. 12-15-80

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 23 TWP. 14s RGE. 18w E/W  
Location as in quarters or footage from lines:  
NE NE NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Ed Leiker  
Lease Name Binder #1 Well No. \_\_\_\_\_  
Office Address Box 17, Munjor Route, Hays, Ks. 67601  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 2/9/83  
Plugging completed 2/11/83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3600'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1159'	none
				4 1/2"	3527'	2557'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Ran sand to 3400' & ran 4 sacks cement. Shot casing at 2592', & 2500'.  
Pulled 63 joints. Plugged well with 4 sacks hulls, 15 gel, 65 cement,  
5 gel, 1 hull, 8 5/8 plug, & 100 sacks 50/50 pos. 4% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1983



My Commission expires \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
February 28 1983  
02-28-83  
CONSERVATION DIVISION  
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. Box 506  
Russell, Kansas 67665

15-051-22395-00-00

DRILLERS LOG

OPERATOR: Edward P. Leiker  
P. O. Box 17, Munjor Rt.  
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas

LEASE: Binder WELL: #1

LOCATION: NE NE NE  
Section 23-14S-18W  
Ellis County, Kansas

Total Depth: 3600'

Elevation:

Commenced: 6-25-81

Completed: 7-2-81

Casing: 8-5/8" @ 1159' with 500 sks cement  
4-1/2" @ 3527' with 175 sks cement

Status: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	40'	Lime & Shale	2432'
Sand & Pyrite	1149'	Lime, Shale & Redrock	2604'
Anhydrite	1191'	Lime & Shale	3001'
Shale	1420'	Lime	3147'
Sand & Shale	2161'	Lime & Shale (R.T.D.)	3600'


STATE OF KANSAS )  
                  ) ss:  
COUNTY OF RUSSELL)


I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

  
Joe K. Branum

Subscribed and sworn to before me this 7th day of July, 1981.

My Commission Expires: February 6, 1984.



  
Notary Public

15-051-22395-00-00

WELL PLUGGING RECORD CARD

MA

December 17, 1982

3049-2'

Ed Leiker  
Box 17  
Munjor Route  
Hays, KS 67601

Binder #1  
NE NE NE  
Sec. 23-14S-18W  
Ellis  
T.D. 3600'

\$115.00

DATE PAID  
(1) \_\_\_\_\_ (2) \_\_\_\_\_  
PAST DUE/ NOTICES SENT

TOTAL DEPTH

~~12-15-82~~ ~~12-17-82~~ ~~12-17-82~~ ~~12-15-82~~ ~~2-28-83~~ ~~2-11-83~~  
APP'L REC'D    PERMISION DATE    LOG REC'D    WPR REC'D    DATE PLUGGED    CORRECTIONS

WELL CLASS:

GAS    X OIL    SWD    INPIJT    D&A    OTHER

Dist # 6  
AGENT

3-14-83  
D.A. REPORT REC'D

15-051-22,783-  
API NUMBER