

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1964  
08-18-64  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Flake of Woodman-Iannitti Drlg. Co., has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti et al,

Complete Address: 706 Union National Bldg., Wichita, Kansas

Lease Name: Pfannenstiel Well No. 1

Location: C NW NW Sec. 24 Twp. 14 Rge. 18 (E)(W) X

County Ellis Total Depth 3690 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Flake was instructed to plug the well as follows:

RTD 3690 8 5/8 csg. set at 202' cwc.

Gun pits, circulate heavy mud, set cementing plug at 540 Ft.

and displace 25 sc cement thru drill pipe. Heavy mud to 195 Ft. set

cementing plug and displace 20 sc cement thru drill pipe. Heavy mud

to 40 Ft. set cementing plug 1/2 sc hulls and 8 sc cement to base of  
celler. Plug rat hole with 2 sc cement.

Very truly yours,

[Signature]  
Conservation Division Agent