



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buchart of Sage Drlg. has this date requested permission to plug the following described well:

Mr. Buchart guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Co.

Complete Address: 4th Floor Petroleum Bldg., Tulsa, Okla.

Lease Name: Daniel M. Pfeifer Well No. 1

Location: NW NE NW Sec. 7 Twp. 14 Rge. (E)(W) 18

County: Ellis Total Depth 3750 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buchart was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 500' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Massey
Conservation Division Agent