

State of Kansas



FORM CP-2

15-051-22597-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Leroy Hicks of Kandrilco, L.T.D. has this date requested permission to plug the following described well:

Operator's Full Name: Rupe Oil Company, Inc.

Complete Address: P. O. Box 2273, Wichita, Kansas 67201

Lease Name: Fort Hays State Well No. #1

Location: NW/NE/NE Sec. 7 Twp. 14 Rge. 18 (E) (W)

County: Ellis Total Depth: 3750'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Leroy Hicks was instructed to plug the well as follows:

8 5/8"-236' s.p. cuc. w/175 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

- 1st plug @ 720' w/70 sacks cement
- 2nd plug @ 210' w/40 sacks cement
- 3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.
- 5 sacks of cement in rat hole and 5 sacks of cement in shoe hole.

Very truly yours, STATE CORPORATION COMMISSION

[Signature]
Conservation Division Agent
OCT 26 1981
10-26-81
CONSERVATION DIVISION
WICHITA, KANSAS