

State of Kansas



15-051-30260-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 20 1966

06-20-66  
CONSERVATION DIVISION  
Wichita, Kansas  
has this

Dear Sir:

Mr. Cook of Ambercrombie Inc.

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Ambercrombie Inc.

Complete Address: 801 Union Center Wichita, Kansas

Lease Name: Fort Hays State College Well No. 1

Location: NW SW SW Sec. 6 Twp. 14 Rge. 18 (E)(W) X

County: Ellis Total Depth 3766 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540 Ft.  
and displace 25 sax cement thru drill pipe. Heavy mud to 250 Ft. set  
cementing plug and displace 20 sax cement thru drill pipe. Heavy mud  
to 40 Ft. set cementing plug, 1/4 sax hulls, and 10 sax cement to base  
of celler. Plug rat hole with 2 sax cement.

Very truly yours,

[Signature]  
Conservation Division Agent