



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 10 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe McGarrah of National Assoc. Petr. Co., has this date requested permission to plug the following described well:

Mr. McGarrah guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: 4th Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name: R. H. Steele Trustees Well No. 1-A

Location: NW-SW-SE Sec. 15 Twp. 14 Rge. (E)(W) 32

County: Logan Total Depth 4965 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. McGarrah was instructed to plug the well as follows:

152'--8 5/8" Surface pipe, cement circulated.
Top of Dakota section @ 600'.

Circulate hole with heavy mud. Pull DP to 825' and displace 100 Sx.
cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent