



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date June 3, 1960, authorized the following plugging operation:

Operator's Full Name: Schoper Air Corp

Complete Address: 404 Grand Fed Okla City, Okla

Lease Name: Fats Paulas Well No. 1

Location: New Pitts New Sec. 7 Twp. 14 Rge. 36 (E) (W)

County: Logan Total Depth: 510.3

Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Jet Pitts circulate hole with heavy mud, set cementing plug at 600 ft and displace 20 sac cement thru drill pipe, heavy mud to 260 ft set cementing plug and displace 20 sac cement, heavy mud to 40' set and tie cementing plug in place with wire, dump 1/2 sac hulls and 10 sac cement, cementing to base of cellar.

RECEIVED STATE CORPORATION COMMISSION

JUN 7 1960

CONSERVATION DIVISION Wichita, Kansas

Very truly yours Gilbert P. Leiker

Signed: Gilbert P. Leiker Conservation Division Agent