

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Curtis Gabel  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Plattsmouth Depth to Top: 3348 Bottom: 3352 T.D. \_\_\_\_\_  
Tor Depth to Top: 3411 Bottom: 3414 T.D. \_\_\_\_\_  
KCB Depth to Top: 3462 Bottom: 3467 T.D. \_\_\_\_\_  
KCF 3505 3508

API No. 15 - 051-21,608 • 00 • 00  
Spot Description: \_\_\_\_\_  
SE SE SW Sec. 18 Twp. 13 S. R. 19  East  West  
4,950 / Feet from  North /  South Line of Section  
2,310 / Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Disney / Well #: 1-18  
Date Well Completed: 12-5-78  
The plugging proposal was approved on: 7-8-11 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Plugging Commenced: 7-13-11  
Plugging Completed: 7-16-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	224'	0
		Production	4 1/2	3810'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perf Tech. Perf 2050' and 1450', 2 holes per setting. Run tubing to 3400'. Mix 100 sks 60/40 pos 4% gel w/250# hulls. Pull to 2000'. Mix 160 sks circulate cement to surface. Pull tubing. Top off w/25 sks. Hook up to 8 5/8, press to 500#. KCC Rep. Marvin Mills. Well plugged at 1:30 P.M.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Curtis Gabel  Employee of Operator or  Operator on above-described well.  
(Print Name)

RECEIVED  
JUL 20 2011

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: \_\_\_\_\_