

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD #1  
K.A.R.-82-3-117

API NUMBER 15-071-20467-0000

LEASE NAME Gould

WELL NUMBER A-2

550 Ft. from S Section Line

3720 Ft. from E Section Line

SEC. 14 TWP. 18 SRGE. 43 (E) or (W)

COUNTY Greeley

Date Well Completed 2-27-89

Plugging Commenced 2-26-89

Plugging Completed 2-27-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murphy Drilling Corp. Exploration Corporation  
ADDRESS Two Energy Square, #1100, Dallas, TX 75206

PHONE # (214) 363-6993 OPERATORS LICENSE NO. 10015

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation N/A Depth to Top N/A Bottom N/A T.D. 5320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS N/A

CASING RECORDS

RECEIVED

CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out

MAR 08 1989  
3-8-89  
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Mud from TD to 2750 50 sx of 60/40 poz, 6% gel from 2750-2650, mud to 1700, 80 sx from 1700-1600, mud to 470', 50 sx from 470-370, mud to 280, 50 sx from 280-180 mud to 40', 10 sx from 40' to surface, 15 sx in rathole, 10 sx in mousehole. Cut off and cap 3' below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementers License No. \_\_\_\_\_

Address Ness City, KS

STATE OF Kansas COUNTY OF Seward, ss.

R. F. BURKE (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) RFB

R. F. BURKE


(Address) P.O. Box 1162, Liberal, KS 67905-1162

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1989

Jody Phelps

JODY PHELPS Notary Public

My Commission Expires: 1-28-91



Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 02 15 89 Approx: S/2 - SW 14 18 43 East  
month day year Sec Top S, Rg X West

OPERATOR: License # 6033  
Name: Murfin Drilling Company  
Address: 250 N. Water, Suite 300  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jack E. Goss  
Phone: 316-267-3241

CONTRACTOR: License #: 6033  
Name: Murfin Drilling Company

Well Drilled For: Well Class: Type Equipment:  
X Oil Inj Infield Mud Rotary  
Gas Storage Pool Ext. Air Rotary  
OAWO Disposal X Wildcat Cable  
Seismic: # of Holes

If OAWO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, total depth location:

550 feet from South line of Section  
3720 feet from East line of Section  
(Note: Locate well on Section Plat Below)  
County: Greeley  
Lease Name: Gould Well # A #2  
Field Name: Wildcat  
Is this a Prorated Field? yes X no  
Target Formation(s): Morrow  
Nearest lease or unit boundary: 550'  
Ground Surface Elevation: Est. 3900' foot MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 1500'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 400  
Length of Conductor pipe required: N/A  
Projected Total Depth: 5300  
Formation at Total Depth: St. Genevieve  
Water Source for Drilling Operations:  
well farm pond X other

DVR Permit #:  
Will Cores Be Taken? yes X no  
If yes, proposed zone:

Washed in 2-17-89

set 400' 200' Act 2 leg.

AFFIDAVIT

MAY Ramsey  
PUSHER  
drilling @  
TD 462.0 FORMATION MISS.  
TD=5320' SURFACE PIPE 8 7/8 @ 4136  
ANHYDRITE 2728' ELEVATION 3896  
STARTING TIME & DATE 6:30 A.M. 2-27-89  
COMPLETION TIME & DATE 12:00 P.M. 2-27-89  
1st PLUG @ 2750 FT. WI 50 SX  
2nd PLUG @ 1700 FT. WI 80 SX  
3rd PLUG @ 4170 FT. WI 50 SX  
4th PLUG @ 40 FT. WI 10 SX  
RAT HOLE CIRCULATED WI 15 SX  
MOUSE HOLE CIRCULATED WI 10 SX  
WATER WELL PLUGGED WI none  
CEMENT COMPANY Libby 100-40-670  
TECHNICIAN

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 07 1989  
CONSERVATION DIVISION  
Wichita, Kansas

5280	4950	4620	4290	3960	3630	3300	2970	2640	2310	1980	1650	1320	990	660	330
------	------	------	------	------	------	------	------	------	------	------	------	------	-----	-----	-----

1650  
1320  
990  
660  
330  
JAN 27 1989  
Agent: \_\_\_\_\_

- REMEMBER TO:
- File Application (form COP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.