

API NUMBER 15-071-20,561-0000

LEASE NAME Sell

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 13-31

1980 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 13 TWP. 18 SRGE. 43 (E) or (W)

LEASE OPERATOR MW Petroleum Corporation

ADDRESS 1700 Lincoln, Ste. 1900, Denver, CO 80203

COUNTY Greeley

PHONE# (303) 837-5000 OPERATORS LICENSE NO. 30868

Date Well Completed --

Character of Well D&A

Plugging Commenced 4/30/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/1/92

The plugging proposal was approved on April 30, 1992 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation N/A Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	514'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Base of anhydrite 2602' with 50 sxs 60/40 Pozmix

1700' with 80 sxs 40' with 10 sxs
850' with 50 sxs 15 sxs rathole
540' with 50 sxs 10 sxs mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No.

Address Lamar, Colorado

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MW Petroleum Corporation

STATE OF Colorado COUNTY OF Denver, ss.

Dave H. Gibbons (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D. H. Gibbons

(Address) 1700 Lincoln, Ste. 1900
Denver, Colorado 80203

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 92

My Commission Expires: January 13, 1993

Notary Public Caryn D. App

RECEIVED
 STATE CORPORATION COMMISSION
 5-18-92 MAY 18 1992
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 05-88

State of Kansas

NOTICE OF INTENTION TO DRILL

971-20,561-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

EFFECTIVE DATE: 4-19-92
DISTRICT # 1
SEAT Yes No

Expected Spud Date 5 1 1992
month day year

Spot SW NW SW Sec 13 Twp 18S S. Rg 43 X East West

OPERATOR: License # 30868
Name: MW Petroleum Corporation
Address: 1700 Lincoln, Ste. 1900
City/State/Zip: Denver, CO 80203-4519
Contact Person: D. H. Gibbons
Phone: 303-837-5425

1980' feet from South North line of Section
330' feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: TO BE DETERMINED
Name: Chapman

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Greeley
Lease Name: Sell Well # 13-31
Field Name: Wildcat
Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Morrow
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 3382 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 2500' 1675'
Surface Pipe by Alternate: 1 XX 2
Length of Surface Pipe Planned to be set: 500'
Length of Conductor pipe required: N/A
Projected Total Depth: 5307'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
well farm pond X other

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWO Disposal Wildcat Cable
Seismic # of Holes Other
If OWO: old well information as follows:
Operator: N/A
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Exp. 10/14/92

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Gale Kuffner
SPUD DATE 4-23-92 INIT. ml
LENGTH SURFACE PLANNED 500
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? N SIZE HOLE _____
SURFACE PIPE 2 1/2 @ 5 1/4 CONDUCTOR _____
ANHYDRITE T- B-2100 ELEVATION _____
TD 300 FORMATION MISS.
RAN PIPE @ SX DV TOOL _____ ALT II DONE _____
Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ _____ Ft. W/ _____ SX
1 Anhydrite Base @ 2602 7600 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1700 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 850 Ft. W/ 50 SX
4 Bottom Surface @ 540 Ft. W/ 50 SX
5 40' Plug @ 40' Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/10 SX
WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____
TECHNICAL SP DATE 4-30-92
STATE OF KANSAS
CONSERVATION DIVISION
RECEIVED
STARTING TIME _____ DATE 4-20-92
COMPLETION TIME 12:30 (AM/PM) DATE 5-1-92
CEMENT COMPANY Halliburton