

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20,619-0000

LEASE NAME Lawson

WELL NUMBER 10-12

1850 Ft. from S Section Line

1950 Ft. from E Section Line

SEC. 12 TWP. 18S RGE. 43 (E/W)

COUNTY Greeley

Date Well Completed 3/1/94

Plugging Commenced 3/1/94

Plugging Completed 3/1/94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Axem Resources, Inc.

ADDRESS 7800 E. Union Ave., Suite 1100, Denver, CO 80237

PHONE# (303) 740-9000 OPERATORS LICENSE NO. 31155

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-1-94 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	315'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 5250'-2630' 50 sks cement @ 330'

50 sks cement @ 2630' 10 sks cement @ 40'

80 sks cement @ 1700' 15 sks in rathole

50 sks cement @ 850' 10 sks in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Axem Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature] RECEIVED

Kyle B. Branum STATE CORPORATION COMMISSION

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 1st day of March 3-3-94 94

GLEND A. R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-96

[Signature] CONSERVATION DIVISION  
Glenda R. Tiffin, Notary Public  
Wichita, Kansas



15-071-20619-0000

EMPHASIS OIL OPERATIONS  
A Division of N-B Company, Inc.  
P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Axem Resources, Inc.  
7800 E. Union Ave., Ste. 1100  
Denver, Colorado 80237

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Lawson WELL #10-12

LOCATION: NW SE  
Section 12-18S-43W  
Greeley County, Kansas

LOGGERS TOTAL DEPTH: 5249'

ROTARY TOTAL DEPTH: 5250'

COMMENCED: 2/19/94

CASING: 8-5/8" @ 315' w/200 sks cement

ELEVATION: 3864' K.B.

COMPLETED: 3/1/94

STATUS: Dry hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	510'	Cherokee	4645'
Stone Corral	2374'	Atoka	5002'
Shale	2609'	Morrow	5075'
Lansing-Kansas City	3947'	Mississippi	5200'
Fort Scott	4320'	R.T.D.	5250'


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on March 1, 1994.

My commission expires: February 6, 1996.

  
GLENDA R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-96

  
Glenda R. Tiffin, Notary Public

RECEIVED  
CONSERVATION COMMISSION  
MAR 03 1994

CONSERVATION DIVISION  
Wichita, Kansas