

API NUMBER 15-071-20,503-0000

LEASE NAME JOHNSON-MOORE

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1-25

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 25 TWP. 18 SRGE. 43 (E-W)

COUNTY Greeley

Date Well Completed 04-12-90

Plugging Commenced 04-13-90

Plugging Completed 04-13-90

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300, Wichita, Ks. 67202

PHONE# (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well DRY

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-13-90 (date)

by Mike Spain - Dodge City (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8-5/8"	618'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

50 sx @ 2550', 80 sx @ 1275', 50 sx @ 650', 10 sx @ 40', 15 sx in rathole, 10 sx in mousehole.  
60/40 poz mix, 6% gel. Job Complete: 10:30 pm 4-13-90 - BJ Titan. Orders by: Mike Spain  
Dodge City, Ks

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300, Wichita, Ks. 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

C. Scott Robinson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Scott Robinson

(Address) 250 N. Water, Suite 300, Wichita, Ks. 67202



SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 90

Glenda G. Newell  
 Glenda G. Newell Notary Public

My Commission Expires: 7-2-93

FORM MUST BE TYPED

EFFECTIVE DATE: 3/27/90

State of Kansas

NOTICE OF INTENTION TO DRILL

011-20, 503-0000 FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 3-26-90  
month day year

SW SW NW Sec 25 Twp 18S S, Rg 43 East West

OPERATOR: License # 6033  
Name: Murfin Drilling Company  
Address: 250 N. Water, Suite 300  
City/State/Zip: Wichita, Ks. 67202  
Contact Person: Scott Robinson  
Phone: 316-267-3241

2970' feet from South line of Section  
4950' feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 6033  
Name: Murfin Drilling Company

County: Greeley  
Lease Name: JOHNSON-MOORE Well #: 1-25  
Field Name: unknown

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OAWO ... Disposal  Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes  no  
Target Formation(s): MOBROW  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: WILL ADVISE feet MSL  
Domestic well within 330 feet: ... yes  no  
Municipal well within one mile: ... yes  no  
Depth to bottom of fresh water: 100'  
Depth to bottom of usable water: 1550'  
Surface Pipe by Alternate: ... 1  2  
Length of Surface Pipe Planned to be set: 550'  
Length of Conductor pipe required: 5300  
Projected Total Depth: 5300  
Formation at Total Depth: MISA  
Water Source for Drilling Operations:  
... well ... farm pond  other

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes ... no  
If yes, total depth location: 2x. 9-22-90

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: ... yes  no  
If yes, proposed zone: 200' MIN INT. II

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

- 1. The appropriate district office shall be notified before setting surface pipe;

PUSHER Raboy Face  
TD 5262 FORMATION M.S.  
SURFACE PIPE 8 7/8 @ 618  
ANHYDRITE 2549 ELEVATION \_\_\_\_\_  
STARTING TIME & DATE 8:00 p 4-13-90  
COMPLETION TIME & DATE 10:30p 4-13-90  
1st PLUG @ 2550 FT. W/ 50 SX  
2nd PLUG @ 1275 FT. W/ 80 SX  
3rd PLUG @ 650 FT. W/ 50 SX  
4th PLUG @ 40-0 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ 10 SX  
WATER WELL PLUGGED W/ \_\_\_\_\_ SX  
CEMENT COMPANY BT Titan  
TECHNICIAN M.S.  
TYPE OF CEMENT 60/40 bag  
Spud 4-1-90  
Set 590-600' 8 7/8

5280  
4950  
4620  
4290  
3960  
3630  
3300  
2970  
2640  
2310  
1980  
1650  
1320  
990  
660  
330  
0  
CONSERVATION DIVISION  
Wichita, Kansas

- Apply for application (form LUP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.