

API NUMBER 15-071-20478-0000

LEASE NAME Dittmer

WELL NUMBER #1

4950' Ft. from S Section Line

2970' Ft. from E Section Line

SEC. 26 TWP. 18S RGE. 43W (E) or (W)

COUNTY Greeley

Date Well Completed 02/09/90

Plugging Commenced 12/29/92

Plugging Completed 12/30/92

RECEIVED  
 KANSAS CORPORATION COMMISSION

JAN 08 1993  
 1-8-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

CONSERVATION DIVISION  
 WICHITA, KS

LEASE OPERATOR MW Petroleum Corporation

ADDRESS 1700 Lincoln St., Ste. 2000, Denver, CO 80203

PHONE# (303) 837-5000 OPERATORS LICENSE NO. 30868

Character of Well Temp. Abandoned

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/14/92 (date)

by Steve Middleton and Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5,009' Bottom 5,110' T.D. 5,350'

Show depth and thickness of all water, oil and gas formations. PBTD 5,258'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Sfc.	502'	8-5/8"		
		502'	5340'	5-1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set PU & tally in hole w/2-3/8" tbq to 5,000'. RU cementer. Load up csg. w/drilling mud. P LD tbq & spot cement plugs: 20 sx @ 5,000'; 20 sx @ 2,400'; 20 sx @ 1,550'; and 5 sx @ 40' to Sfc. NU to broaden head. Pressured to 1,500 psi. Held. P&A completed @ 3:30 p.m. 12/30/92.

Name of Plugging Contractor JW Gibson Well Service License No. 05866

Address 1204 E. Burlington, Fort Morgan, CO 80701 303-867-3058

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MW Petroleum Corporation

STATE OF Colorado COUNTY OF Denver, ss.

D. H. Gibbons (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D.H. Gibbons

(Address) 1700 Lincoln, Denver, CO 80203

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 93

Lynn C. Taylor  
 Notary Public Lynn C. Taylor

My Commission Expires: 11-8-96

USE ONLY ONE SIDE OF EACH FORM