

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33365
Name: Layne Energy LLC
Address 1: 1900 Shawnee Mission Parkway
Address 2: _____
City: Mission Woods State: KS Zip: 66205 + 2001
Contact Person: Victor H Dyal
Phone: (913) 748-3960
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: D-27,322
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 2058 Bottom: 2067 T.D. 2100
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 019-26445-00-00
Spot Description: _____
SW W2 E2 SE Sec. 10 Twp. 33 S. R. 13 East West
1,320 Feet from North / South Line of Section
1,155 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Chautauqua
Lease Name: Ownbey Well #: 1-A SWD
Date Well Completed: _____
The plugging proposal was approved on: 7-20-11 (Date)
by: John Almound (KCC District Agent's Name)
Plugging Commenced: 7-21-11
Plugging Completed: 7-21-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface pipe		Two joints	8-5/8	40'	none
Arbuckle lime	2058-2067'	Production	4-1/2	2100	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up ran 2-3/8 tubing to 2080' pumped gel spacer pumped 10 sacks 60/40 POZ cement. Pulled pipe to 650', pumped another 10 sacks cement. pulled pipe to 323'. Pumped 55 sacks cement pump 323' to surface, job complete rig down. Pumped total of 75 sacks cement.

Plugging Contractor License #: 31440 Name: Consolidated Oil Well Services
Address 1: 820 E 7th Address 2: _____
City: Eureka State: KS Zip: 67045 + _____
Phone: (620) 583-7664
Name of Party Responsible for Plugging Fees: Layne Energy LLC
State of Kansas County, Montgomery, ss.
Jacob McClain Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUL 25 2011

KCC WICHITA