

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD JUL 19 2010
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: JOHN O. FARMER, INC.
Address: P.O. Box 352 Russell, KS 67665
Phone: (785) 483-3145, Ext. 214 Operator License #: 5135
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/21/2010 (Date)
by: Marvin Mills (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 167-23,635-00-00
Lease Name: THOMPSON "B"
Well Number: 1
Spot Location (QQQQ): SE - NE - NW - NE
495 Feet from North / South Section Line
1540 Feet from East / West Section Line
Sec. 15 Twp. 11 S. R. 15W East West
County: Russell
Date Well Completed: 6/22/2010
Plugging Commenced: 4:15AM 6/22/2010
Plugging Completed: 8:00AM 6/22/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	220.75'	8 5/8"	220.75'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 3367'W/25sks 5th Plug @ 40'W/10sks Circulated 1st Plug 15 Minutes W/56 Vis MUD
2nd Plug @ 990'W/25sks 30sks In Rat Hole Plugs displaced with mud
3rd Plug @ 540'W/90sks 15sks In Mouse Hole Total 235sks 60/40Poz 4%GelW $\frac{1}{2}$ #CF/sk
4th Plug @ 270'W/40sks By Quality Oilwell Cementing-Completed @ 8:00AM 6/22/2010


Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
Address: P.O. Box 763 Hays, KS 67601
Name of Party Responsible for Plugging Fees: JOHN O. FARMER, INC.
State of Kansas County, Russell, ss.

John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer III
(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 15th day of July, 2010

Margaret A. Schulte My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AR

HP