

RECEIVED

JUL 19 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION KCC WICHITA WELL PLUGGING RECORD K.A.R. 82-3-117

Form CG-4 March 2008 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34318 Name: BEREXCO.LLC Address 1: PO BOX 723 Address 2: PO BOX 20380 - WICHITA, KS 67206 City: HAYS State: KS Zip: 67601 Contact Person: MARK LEIKER Phone: (316) 772-8649 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): TORONTO LKC Depth to Top: 3628 3722 Bottom: 3638 3884 T.D.

API No. 15 - 063-21052-00-00 Spot Description: SE SE NE Sec. 28 Twp. 15 S. R. 27 East West 2,970 Feet from North South Line of Section 330 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: GOVE Lease Name: SARALEE Well #: 1 Date Well Completed: 9/4/86 The plugging proposal was approved on: 6/30/10 by: DARYL DIPMAN (KCC District Agent's Name) Plugging Commenced: 6/30/10 Plugging Completed: 6/30/10

Show depth and thickness of all water, oil and gas formations.

Table with 2 main columns: Oil, Gas or Water Records and Casing Record (Surface, Conductor & Production). Rows include LKC formation with SURFACE and PRODUCTION casing data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU Bx Rig #12 and Bx workstring #44. TIH to 3700'. Pump 15 sx gel and 75 sx 60/40/POZ cement w/4% gel. Pull up to 1905' and pump 100 sx 60/40 POZ cement w/4% gel and 100# hulls. No circulation. Pull up to 824' and pump 100 sx 60/40 POZ cement w/4% gel and 100# hulls. No circulation. Pull tubing to 412' and pump 30 sx 60/40 POZ cement w/4% gel. Circulated cement to surface. TOH w/tbg. Top off casing w/ 1 sx cement. Tie onto 8 5/8 and pump 12 sx down annulus. Rig down. Job witnessed by KCC.

Plugging Contractor License #: 34318 Name: BEREXCO LLC Address 1: PO BOX 723 Address 2: PO BOX 20380 - WICHITA, KS 67206 City: HAYS State: KS Zip: 67601 Phone: (785) 628-6101 Name of Party Responsible for Plugging Fees: BEREXCO LLC State of: KANSAS County: SEDGWICK MARK LEIKER Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Leiker