

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

RECEIVED  
JUL 30 2010  
KCC WICHITA  
Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34314  
Name: JAMEX, Inc.  
Address 1: 2871 Lake Vista Dr., #200  
Address 2: \_\_\_\_\_  
City: Lewisville State: TX Zip: 75067 + \_\_\_\_\_  
Contact Person: Paula D. Clark  
Phone: (214) 265-7141 ext. 120  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
NA Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 203-20153-00-00  
Spot Description: \_\_\_\_\_  
NW NW SW NE Sec. 21 Twp. 20 S. R. 38  East  West  
1,406 Feet from  North /  South Line of Section  
2,361 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: WICHITA  
Lease Name: Heath-Spradling Well #: 1  
Date Well Completed: 5/21/10  
The plugging proposal was approved on: 5/22/10 (Date)  
by: Richard Lacey (KCC District Agent's Name)  
Plugging Commenced: 5/22/10  
Plugging Completed: 5/22/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	327'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CONTACTED KCC FOR PLUGGING ORDERS, RECEIVED PLUGGING ORDERS FROM KCC REP RICHARD LACEY, TOOH W/ 4 STDS DP, ND BOP'S, TIH W/OPEN ENDED DRILL PIPE TO 5650', ALLIED CEMENTING ON LOCATION. RU ALLIED, MIX & PUMP 50 SKS PLUG OF 60/40 POZ CMT w/ 4% GEL & 1/4# FLO-SEAL PER SACK, MIXED 12.8 PPG, YIELD 1.47 CU/FT PER SACK & MIX WATER 6.90 GPS. NOTE: ALL CMT PLUGS MIXED WITH SAME TYPE CMT, SAME CMT MIXTURE, AND ALL DISPLACED FROM DRILL PIPE WITH DRLG MUD, LD DP TO 1280', PUMP 60 SACKS OF CMT PLUG, LD DP TO 600', PUMP 50 SACKS CMT PLUG, LAY DN DP TO 360', PUMP 50 SACKS CMT PLUG, LD DP TO 60', PUMP 20 SACKS CMT PLUG AND PLUG MOUSEHOLE WITH 20 SACKS CMT PLUG, CIRCULATE CMT TO SURFACE, PLUG RATHOLE WITH 30 SACKS CMT PLUG AND PLUG MOUSE HOLE WITH 20 SACKS CMT PLUG, PLUGGING JOB COMPLETE AT 6:30 PM 5/22/10.

Plugging Contractor License #: NA Name: Allied Cementing Co, LLC  
Address 1: P.O. Box 31 Address 2: \_\_\_\_\_  
City: Russell State: KS Zip: 76665 + \_\_\_\_\_  
Phone: (785) 483-3887  
Name of Party Responsible for Plugging Fees: JAMEX, Inc.  
State of Texas County, Denton, ss.  
John Harris  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: John C. Harris

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten initials]*