

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34131
Name: Dave Holke Consulting, Inc.
Address 1: PO Box 1309
Address 2: 120 Stone Forest
City: Fredericksburg State: TX Zip: 78624 +
Contact Person: David C. Holke
Phone: (830) 990-4050
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 5453' Bottom: 5470' T.D. 5633'

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 025-21492-00-0
Spot Description: _____
SE NE SW SE Sec. 10 Twp. 34 S. R. 21 East West
702 Feet from North / South Line of Section
1,626 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Clark
Lease Name: Bouziden Well #: 1-10
Date Well Completed: 2/25/10
The plugging proposal was approved on: 4/18/11 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Plugging Commenced: 4/18/11
Plugging Completed: 4/21/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Conductor	20	75	0
		Surface	8 5/8	639	0
		Production	4 1/2	5628	4516

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 5400' and dumped 2 sacks cement on top of CIBP. Cut off casing at 4516' and circulated hole full of mud. Pulled and layed down casing to 1100'. Set cement plugs (60/40 pozmix with 4% gel) through casing and set as follows while laying down casing: 50 sacks @ 1100', 50 sacks @ 650', 50 sacks @ 300', 50 sacks @ 60' to surface. Had 100 % returns while setting all plugs.

KERR WELL SERVICES, INC.

Plugging Contractor License #: 34131 32722 Name: Dave Holke Consulting, Inc.
Address 1: PO Box 1309 Address 2: 120 Stone Forest
City: Fredericksburg State: Texas Zip: 78624 +
Phone: (830) 990-4050
Name of Party Responsible for Plugging Fees: Dave Holke Consulting, Inc.
State of Texas County, Gillespie, ss.
David C. Holke Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: [Signature]

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAY 10 2011
KCC WICHITA