


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15051-20021-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 35 Twp. 13S Rge. 20 (W)
Location as "NE/CNW/SW" or footage from lines NW NE
Lease Owner Texaco Inc.
Lease Name J. A. Engel, Jr. Well No. 4
Office Address 614 Bitting Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-12-1967
Application for plugging filed 3-14-1967
Application for plugging approved 3-15-1967
Plugging commenced 3-11-1967
Plugging completed 3-11-1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Dry Hole Depth to top Bottom Total Depth of Well 3918 Feet
Show depth and thickness of all water, oil and gas formations. PBD 2774

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dry Hole				8-5/8"	417'	None
				5-1/2"	2805'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: 2774-920 w/hvy mud, 920-800 w/15 sxs cmt, 800-400 w/hvy mud, 400-0 w/50 sxs cmt. Comp 11:10 AM 3-11-67.

RECEIVED
STATE CORPORATION COMMISSION

APR 7 1967

4-7-67

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Texaco Inc.
Address Box 660, Hays, Kansas 67601

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. E. Anderson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. E. Anderson
614 Bitting Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April 1967

My commission expires 10-13-69

Leggy Sue Jones
Notary Public.

DRILLER'S LOG

COMPANY: Texaco, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: J. A. ENGEL, JR. #4
 LOCATION: C NW NE SEC. 35-13S-20W
 ELLIS COUNTY, KANSAS
 COMMENCED: 2-24-67
 COMPLETED: 3-4-67

15.051.20024.00.00

0	10	Clay, Postrock
10	75	Rock, Clay
75	424	Shale, Shells
424	470	Shale
470	975	Shale, Shells, Sand
975	1215	Sand
1215	1505	Shale, Shells
1505	1553	Anhydrite
1553	2070	Shale, Shells, Lime
2070	2620	Lime, Shale
2620	2965	Shale, Lime
2965	3275	Lime, Shale
3275	3845	Lime
3845	3870	Sand, Chert
3870	3918	Sand, Lime
	<u>3918</u>	<u>RTD - Set 5 1/2" Casing</u>

MAR 15 1967
 CONSERVATION DIVISION
 WICHITA, KANSAS

8 5/8" surface casing set @ 424' cemented with 350 sacks 50/50
 sacks Posmix, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the J. A. Engle, Jr. #4 Well,
 located C NW NE of Section 35, Township 13 South, Range 20 West,
 Ellis County, Kansas, as reflected by the records of Leben Drilling,
 Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS }
 COUNTY OF BARTON } SS

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 6th day of March, 1967.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967