


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-21262-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County. Sec. 35 Twp. 13 Rge. 20 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NW NW NW
Lease Owner Bill Witcraft
Lease Name Storm Well No. 1
Office Address P. O. Box 811, Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed February 17 19 77
Application for plugging filed February 17 19 77
Application for plugging approved February 17 19 77
Plugging commenced February 17 19 77
Plugging completed 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3866'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 600' with 70 sacks 50/50 Pozmix, 2% Gel pumped thru drill pipe
Mud to 185' and 20 sacks cement thru drill pipe-mud to 40' w/1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1977
2-22-77
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Larry Curtis (employee of owner) or (owner/cooperator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1977

Alvord M. Hague
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: February 9, 1977
 DATE COMPLETED: February 17, 1977

Bill Sitcraft
 STORM # 1
 NW NW NW
 Sec 35-T13-R20
 Ellis County, Kansas
 15.051-21262-00-00
 ELEVATION: 2214 K.B.

0 - 60' Post rock, Clay
 60 - 995' Shale
 995 - 1230' Sand
 1230 - 1520' Shale
 1520 - 1564' Anhydrite
 1564 - 3226' Shale and Lime
 3226 - 3461' Lime and Shale
 3461 - 3465' Shale
 3465 - 3484' Shale and Lime
 3484 - 3502' Lime and Shale
 3502 - 3757' Lime
 3757 - 3853' Lime and Shale
 3853 - 3866' Dolomite
 3866' RTD

FORMATION DATA

Anhydrite	1520
Topeka	3226
Hoebner	3461
Toronto	3484
Lansing	3502
Base K.C.	3757
Arbuckle	3853
RTD	3866

SURFACE PIPE:
 Set 8 5/8", used 28# pipe at 205'
 w/150 sacks Common, 2 1/2 Gal, 3 1/2 cc.

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 18th day of February, 1977.

Walter M. Hague
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED
 IN COMMISSION
 FEB 22 1977
 COMMISSION