

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-19428-00-01

LEASE NAME Storm

WELL NUMBER A-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3305 Ft. from S Section Line

3305 Ft. from E Section Line

SEC. 35 TWP. 13 RGE. 20 (E) or (W)

COUNTY Ellis

Date Well Completed

Plugging Commenced 8-24-89

Plugging Completed 8-24-89

LEASE OPERATOR Harold Haselhurst

ADDRESS Rt. 1 Box 69 Hays, Kansas 67601

PHONE# (913) 625-5184 OPERATORS LICENSE NO. 4136

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-20-89 (date)

by Gib Schuck (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8" ID	206	none
				5" ID	3842	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

pumped 200 psi Common Cement follow w/ 200 psi 65% SC per cement
8% Cel down 2" tubing to plug mdy PST 1000 shut in 600 PST
mix and pump 50 psi cement down 2" 200 PST shut in
mix and pump 50 psi cement down 8" Annulus 200 PST shut in
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. _____

Address Box 69 Hays, Ks 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harold's Oil Production

STATE OF Kansas COUNTY OF Ellis, ss.

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
FEB 14 1990
2-14-90
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

(Signature) Harold Haselhurst

(Address) Hays Kansas 67601

WITNESSED AND SWORN TO before me this 8th day of NOVEMBER, 19 89

Martha Schuyman

Notary Public

NOTARY PUBLIC - State of Kansas

MARLENE STUBBS

My Comm. Exp. 9-28-91

My Commission Expires: 9-28-91

C-15,916 ✓

WELL LOG

1505194280001

OPERATOR D. G. Hansen SEC. 35-13-20W
WELL NAME Storm "A" #1 LOC. SE SE NW
TOTAL DEPTH 3843' COUNTY Ellis
COMM. October 3, 1960 COMP. October 14, 1960 STATE Kansas
RIG NO. 1

CASING: Ran 206.61 (10 jts.) 8-5/8" OD. surface casing Elevation - 2207' R.B.
Set 5-1/2" OD casing @ 3842' (119 jts.) PRODUCTION: Producing
cemented with 150 sx.
2-stage from 1543 feet to surface with 400 sx
poemix and 20 cubic feet of strata-creek. ✓

All measurements taken from the top of rotary bushing

FROM	TO	FORMATION	DEVIATION	REMARKS
			FROM VERTICAL	
0	555	Shale-Sand		
555	700	Sand-Shale		
700	1000	Streak Sand-Shale		
1000	1150	Sand		
1150	1280	Shale-Red Bed		
1280	1510	Red Bed-Shale		
1510	1556	Anhydrite		
1556	1740	Shale		
1740	2105	Shell-Shale		
2105	2530	Shale-Lime	0' - 2500	
2530	2590	Lime		
2590	2705	Lime-Shale	0' - 2750	
2705	2800	Shale-Lime		
2800	2885	Lime-Shale		
2885	2980	Shale-Lime	0' - 3000	
2980	3265	Lime-Shale	0' - 3250	
3265	3335	Shale-Lime		
3335	3465	Lime-Shale		
3465	3580	Lime	0' - 3500	
3580	3625	Lime-Shale		
3625	3728	Lime		
3728	3816	Lime-Shale-Chert	0' - 3750	
3816	3822	Lime-Shale-Chert-Arbuckle		DST 3818-3822'
				DST 3819-3833'
3822	3843	Arbuckle		DST 3822-3843'

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1990
CONSERVATION DIVISION
Wichita, Kansas

State Corporation Commission
Rec'd DEC 3 1970 A.P.M.
DAROLD D. MAIN, Secretary