

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6044
Name: Stelbar Oil Corporation, Inc.
Address 1: 1625 N. Waterfront Parkway, Suite #200
Address 2: _____
City: Wichita State: KS Zip: 67206 + 6602
Contact Person: Roscoe Mendenhall
Phone: (316) 440-7605
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lower Keyes Depth to Top: 5336' Bottom: 5360' T.D. 5560'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 187-21090 0000
Spot Description: _____
NE SE NW Sec. 24 Twp. 30 S. R. 41 East West
1,650 Feet from North / South Line of Section
2,070 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stanton
Lease Name: Armstrong Well #: 2-24
Date Well Completed: 05/10/2007
The plugging proposal was approved on: 05/27/2010 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Plugging Commenced: 06/01/2010
Plugging Completed: 06/02/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Lower Keyes</u>	<u>Oil, Gas</u>	<u>Surface</u>	<u>8-5/8"</u>	<u>1702'</u>	<u>-----</u>
<u>5336' - 5360'</u>	<u>Saltwater</u>	<u>Production</u>	<u>5-1/2"</u>	<u>5560'</u>	<u>3020'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb. hulls and 25 sx cement to plug perfs from 5336' to 5360'. Shot and pulled 5-1/2" to 1740'. Circulate hole with mud and mixed 50 sx-plug 1740' to 1590'; 40 sx-plug 600' to 480'; 10 sx-plug 40' to 0'. Capped 8-5/8" 3 feet below ground level.

AR

Plugging Contractor License #: 31151 Name: Sargent and Horton Plugging, Inc.
Address 1: Route #1, Box #49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + .9731
Phone: (580) 854-6515
Name of Party Responsible for Plugging Fees: Stelbar Oil Corporation, Inc.
State of Kansas County, Sedgwick, ss.
Roscoe Mendenhall Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

RECEIVED
JUN 29 2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AR

KCC WICHITA