

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32198  
Name: PETROSANTANDER (USA) INC  
Address 1: 6363 WOODWAY DR # 350  
Address 2: \_\_\_\_\_  
City: HOUSTON State: TX Zip: 77057 + \_\_\_\_\_  
Contact Person: LILIANA HERNANDEZ  
Phone: (713) 784-8700  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Morrow Depth to Top: 4766' Bottom: 4470' T.D. 4920'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 055-21385 *oop* *for use*  
Spot Description: SE SE SE  
SE SE SE Sec. 3 Twp. 23 S. R. 31  East  West  
2,260 Feet from  North /  South Line of Section  
380 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: FINNEY  
Lease Name: TRANS AM S Well #: 1-3  
Date Well Completed: 06-12-1995  
The plugging proposal was approved on: 06-21-2010 (Date)  
by: KEN JEHLIK (KCC District Agent's Name)  
Plugging Commenced: 06-21-2010  
Plugging Completed: 06-22-2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Morrow (4766' - 4470')	Oil	SURFACE	8-5/8"	472'	
		PRODUCTION	5-1/2"	4971'	

Describe in detail the formations in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SET CIBP AT 4705' WITH 2 SACKS CEMENT ON TOP.  
TIH WITH 67 JTS 2 3/8" TBG TO 2115' LOADED WELL WITH SALT WATER  
SPOT 25 SX PLUG 60/40 POZ MIX 4% GEL HAD FULL RETURNS WHILE PUMPING PLUG  
TOH WITH 25 JTS TO 1320' FS AND PUMPED 135 SX CEMENT DID CIRCULATE TO SURFACE  
TOH WITH TBG AND TOP OFF 5 1/2" CSG WITH 30 SX. STAYED FULL TIED ON BS  
AND PUMPED 55 SX DOWN ANNULUS PRESSURED TO 400 PSIG HELD OK.

Plugging Contractor License #: N/A *33961* Name: PETE KUNEYL  
Address 1: 11130 East 7 Mile Rd Address 2: \_\_\_\_\_  
City: Garden City State: KS Zip: 67846 + \_\_\_\_\_  
Phone: (\_\_\_\_) \_\_\_\_\_  
Name of Party Responsible for Plugging Fees: PETROSANTANDER (USA) INC  
State of KANSAS County, FINNEY, ss.  
LILIANA HERNANDEZ  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Liliana Hernandez