

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 31930  
Name: BlueRidge Petroleum Corporation  
Address 1: P.O. Box 1913  
Address 2: \_\_\_\_\_  
City: Enid State: OK Zip: 73702 + 1913  
Contact Person: Jonathan Allen  
Phone: ( 580 ) 242-3732  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3318 Bottom: 3320 T.D. \_\_\_\_\_  
Arbuckle Depth to Top: 3270 Bottom: 3282 T.D. \_\_\_\_\_  
Lansing Depth to Top: 3146 Bottom: 3180 T.D. \_\_\_\_\_

API No. 15 - 009-21719-00-01  
Spot Description: \_\_\_\_\_  
NE NW Sec. 22 Twp. 17 S. R. 11  East  West  
660 Feet from  North /  South Line of Section  
1,980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Soeken Well #: 8  
Date Well Completed: 01/08/1980  
The plugging proposal was approved on: 09/03/2010 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 09/08/2010  
Plugging Completed: 09/08/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	658	0
		Production	5.50	3345	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well as follows: 1st plug @ 3020' w/ 10 sx gel followed by 50 sx cmt w/ 100# hulls, 2nd plug @ 1500', 125 sx cmt w/ 200# hulls, 3rd plug @ 700', 75 sx cmt w/ 100# hulls. TOH w/ tbg & pump 50 sx cmt via csg w/ cement to surface. Total cement 300 sx 60/40 Poz w/ 4% gel, 400# hulls & 10 sx gel. P&A'd 09/08/2010. Plugging witnessed by KCC (Bruce Rodie).

Plugging Contractor License #: 6123 Name: Chase Well Service, Inc.  
Address 1: P.O. Box 355 Address 2: \_\_\_\_\_  
City: Great Bend State: KS Zip: 67530 + 0355  
Phone: ( 620 ) 793-9556  
Name of Party Responsible for Plugging Fees: BlueRidge Petroleum Corporation  
State of Oklahoma County: Garfield ss.  
Jonathan Allen  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jonathan Allen

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 20 2010

KCC WICHITA