


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 35 Twp. 13S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner The Texas Company
Lease Name Leo Storm "B" Well No. 1
Office Address 614 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed August 10 19 55
Application for plugging filed August 10 19 55
Application for plugging approved August 11 19 55
Plugging commenced August 11 19 55
Plugging completed August 11 19 55
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3856 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	270'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED AS FOLLOWS:

3856' to 270' - Heavy Mud
Dry hole plug @ 270'
1/2 Sack Hulls & 25 Sacks Cement to 215'
Heavy Mud to 35'
1/2 Sack Hulls, Dry hole Plug & 10 sacks cement to bottom of cellar

Name of Plugging Contractor Powell Drilling Company
Address 909 Central Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell
614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 55

My commission expires Sept. 20, 1956

H. Howard Kistler Notary Public.

PLUGGING
FILE NO. 25-713-204
BOOK PAGE 141 LINE 38

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1955
8-25-55
CONSERVATION DIVISION
Wichita, Kansas

THE TRIAD COMPANY
Tulsa, Oklahoma

DRILLERS WELL LOG

Log-Name "B" #1

SW SW NW Section 35-138-20N

Ellis County, Kansas

Elevation:

Commenced R.D. 7-27-55

Completed R.D. 8-10-55

Total Depth 3856'

Initial Production: Dry

Contractor: Powell Drilling Co.

Casing Record: 277', 7 jts, spiral weld 20-3/4" surface casing

15:05:00 5:20:00

<u>STRATA</u>	<u>DEPTH</u>
Clay Sand & Chalk	0 - 100
Shale	100 - 790
Sand & Shells	790 - 1155
Shale & Shells	1155 - 1522
Anhydrite	1522 - 1558
Shale & Shells	1558 - 1930
Salt & Shale	1930 - 2040
Shale & Shells	2040 - 2215
Shale & Lime	2215 - 2580
Lime	2580 - 2780
Lime & Shale	2780 - 3252
Lime	3252 - 3856

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

POWELL DRILLING COMPANY

By C. M. Powell, Jr.

Signed and sworn to in my presence this 11th day of August, 1955, by C. M. Powell, Jr., partner in the Powell Drilling Company.

Billie Ann Green

My Commission expires February 5, 1958

LOG OF WELL

FORM PO-214 SHEET 1 (4-54) 35M

15-057-00520-00-00
LEO STORM "B" O/A NO. 1

SHEET 1

OWNER D. G. Hanson - 25%
The Texas Co. - 75% (opr) DIVISION Oklahoma DATE MADE August 24, 1955

DISTRICT Kansas LEASE Leo Storm "B" O/A WELL NO. 1

STATE Kansas COUNTY OR PARISH Ellis TWP. 13S RANGE 20W SEC. 35

LOCATION OF WELL SW SW NW

COMMENCED RIGGING UP 7-27-55 COMMENCED DRILLING 7-27-55 COMPLETED DRILLING 8-10-55

DAY DRILLER _____ NIGHT DRILLER _____ CONTRACTOR Powell Drig. Co.

CABLE FROM _____ TO _____ ROTARY FROM 0' TO 3856' COMPANY RIG NO. _____

TOTAL DEPTH 3856' MEASURED BY N. C. Harrell ELEVATION KB - 2224
DT - 2222
OL - 2219

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS		
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET AT
<u>10-3/4"</u>	<u>29#</u>	<u>270'</u>										<u>FT.</u>
												<u>FT.</u>
												<u>FT.</u>
												<u>FT.</u>
												<u>FT.</u>
												<u>FT.</u>
												<u>FT.</u>

10-3/4" casing set at 270' with 150 sacks cement and 200# CC. Cement circulated.

WAS CASING CEMENTED? _____ IF SO, HOW MANY SACKS OF CEMENT USED? _____

LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____

HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____

REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

Completed Plugging 8-11-55

FLOWING, PUMPING, GASSER OR DRY Dry PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____

KIND OF SHOT _____ SIZE OF SHOT, QUARTS _____

NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____

LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____

BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____

TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBLs. PER DAY _____

PRODUCTION AFTER SHOT _____ BBLs. PER DAY. SHOT FURNISHED BY _____

NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____ (COMPANY EMPLOYEE)

COMMENCED DRILLING DEEPER _____ COMPLETED _____ DRILLING DEEPER _____

TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

REMARKS: _____

RECEIVED
DATE _____ COMMISSION

Leo Storm "B" O/A #1
Pleasant NW Pool
TD 3856'
Completed Drilling 8-10-55
Completed Plugging 8-11-55

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS WHEN, HOW, AND BY WHOM PLUGGED.
STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

PLUGGING
FILE SEC 2573 R 20W
BOOK PAGE 141 LINE 38

TOTAL NUMBER OF SHEETS _____

LOG OF WELL

SHEET No. 2

15.051.00520.00.00

District **Kansas** Owner **D. G. Hansen - 25%**
The Texas Company Farm Leo Storm "B" O/A Well No. 1

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
REMARKS:					
8-8-55					Ran DST #1 from 3810-30', open 25 minutes, recovered 12' slightly oil cut mud, BHP 40# in 20 minutes.
8-9-55					Ran DST #2 from 3829-48', open 1 hour, recovered 15' slightly oil cut mud, BHP 70# in 20 minutes.
8-10-55					Ran DST #3 from 3846-56', open 1 hour, recovered 1680' salt water, BHP 1075#.
8-11-55					Well non-commercial. Plugged and abandoned.
TOPS:					
Cimaron Dolomite--1520					
Topeka-----3212					
Heebner-----3459					
Toronto-----3482					
Lansing-----3499					
Conglomerate-----3810					
Arbuckle-----3842					
2220					
A-1212					
L-1225					