

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-22,992-00-00

LEASE NAME Storm

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 35 TWP. 13 RGE. 20 (E) or (W)

COUNTY Ellis

Date Well Completed est 5/10/82

Plugging Commenced 12/05/95

Plugging Completed 12/05/95

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE#(913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/28/95 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No - sent with CP-1

Producing Formation Lansing-Kansas City Depth to Top 3507' Bottom 3758' T.D. RTD - 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	342	none
				5 1/2	3900	none

RECEIVED
 STATE CORPORATION COMMISSION
 12-8-95
 CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump 40sx 60/40 poz 10% gel w/ 300# hulls followed by 18sx gel, followed by 140sx 60/40 poz 10% gel w/ 100# hulls down 5 1/2" casing - pressured up to 600#, shut in pressure 500#.
Hook up to 8 5/8 - 5 1/2" annulus - pressure to 500#, no entry.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. NA

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 70 Hays, KS 67601



AND SWORN TO before me this 7th day of December, 19 95

Kimberly J. King
 Notary Public
 Kimberly J. King

My Commission Expires: 2-3-98