


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15-051-222/8-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plot

Ellis County, Sec. 35 Twp. 13 Rge. 20 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines _____
C E/2 W/2 NW
Lease Owner J. B. Collins
Lease Name Storm B Well No. 1
Office Address 1007 Cody Ave. Suite A, Hays, KS 67601
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole

Date Well completed 12-31 1980
Application for plugging filed 12-31 1980
Application for plugging approved 12-31 1980
Plugging commenced 12-31 1980
Plugging completed 12-31 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____
19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3866
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	168'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 800' with 70 sacks cement
2nd plug was set @ 240' with 25 sacks cement
3rd plug was set @ 46' with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.

I, Joseph A. Hess, Sec.-Treas of Drlg. Contrc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) Joseph A. Hess
JOSEPH A. HESS, Hays, KS 67601
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 81

My commission expires August 30, 1982

Patty Dreiling
Patty Dreiling
Notary Public.



DREILING OIL, INC.

Victoria, Kansas 67671

WELL LOG

15.05/222/8.00.00

Company J. B. Collins
1007 Cody Ave. Suite A
Hays, KS 67601

Sec. 35 Twp. 13 Rng. 20

Farm Storm ~~A~~ No. 1

Location C E/2 W/2 NW

Total Depth 3866'

County Ellis

Comm. 12-18-80 Comp. 12-31-80

Elevation: 2207' K. B.

Contractor Dreiling Oil, Inc.
Rt. #1
Victoria, KS 67671

2204' D. F.

2202' G. R.

Casing Record

Cement Record

Production:

168' - 8 5/8"

135 sacks cement

D & A


Figures Indicate Bottom of Formations

0'	35'	Top Soil & Post Rock
35'	70'	Post Rock
70'	173'	Shale
173'	1221'	Sand & Shale
1221'	1518'	Shale
1518'	1550'	Anhy.
1550'	1557'	Anhy.
1557'	2160'	Shale & Lime Streaks
2160'	2370'	Shale & Lime
2370'	2568'	Shale & Lime
2568'	2850'	Shale & Lime
2850'	3010'	Shale & Lime
3010'	3062'	Shale & Lime
3062'	3217'	Shale & Lime Streaks
3217'	3345'	Lime
3345'	3450'	Lime
3450'	3540'	Lime
3540'	3608'	Lime
3608'	3690'	Lime
3690'	3725'	Lime
3725'	3795'	Lime
3795'	3866'	Lime
3866'	T.D.	

STATE OF KANSAS)
)
COUNTY OF ELLIS)

JAN 7 1981
CONSERVATION DIVISION

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Storm B #1.


JOSEPH A. HESS

Subscribed and sworn to before me this 5th day of January, 1981.


Patty Dreiling Notary Public

My appointment expires: August 30, 1982.

