

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
WICHITA
05-25-59

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 31-13 County: Ellis 15:051-05397-00-00

Location: CN $\frac{1}{2}$ SE SW Sec. 27 Twp. 13 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3843

I have this date completed supervision of plugging of:

Lease Name: Giebler Well No. 2-B

Operator's Full Name: Imperial Oil of Kans

Complete Address: 780 4th Natl Bk Wichita, Kans

Plugging Contractor: same & Halliburton Cementing Co

Address: _____ License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3:30 PM Day 14 Month 5 Year 59

The above well was plugged as follows:

8 5/8" at 228' circulated with cement - 5 1/2" at 3837' with 225 sax cement
behind - DV tool at 1543' and circulated with cement from 1543' to 0' with
cement- PB to 3750', perforated 3504' - No pipe recovery.

Pumped hole full heavy mud (40 sax Gel), pumped cementing plug to 570',
followed by 70 sax cement - cement 570' to 0' - pump pressure 1400#.

Mudding and cementing by Halliburton Cementing Co.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 27 T. 13 R. 20
BOOK PAGE 3 LINE 13