

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cooperative Refinery Assn 15:05:0000 8:00:00

Complete Address: Drawer C Great Bend, Kans

Lease Name Giebler Well No. 1

Location SW SW SE Sec. 27 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3815

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling & Globe Cementing Co

Address: Great Bend, Kans License No. 49

Operation Completed: Hour 7PM Day 23 Month 6 Year 63

The Above well was plugged as follows:

8 5/8" 238' circulated with cement - 5 1/2" 3810' with 125 sax cement.

Pulled 890' 5 1/2" to 640', circulated hole with heavy gel mud (42 sax

Gel) - displaced 20 sax cement through 5 1/2" at 640', heavy mud to 290'

displaced 20 sax cement through 5 1/2" at 290', heavy mud to 35', cement

35' to botton cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Lacey
Well Plugging Supervisor

DATE 6/26/63

INV. NO. 7219 W