

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1960
06-22-60
CONSERVATION DIVISION
Wichita, Kansas

File No. 15-051-02890-00-00 County: Ellis

Location: SW SW NE Sec. 27 Twp. 13 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3880

I have this date completed supervision of plugging of:

Lease Name: Giebler Well No. C-2

Operator's Full Name: Imperial Oil of Kansas

Complete Address: Box 97 Wakeeney, Kans

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 17 Month 6 Year 20

The above well was plugged as follows:

8 5/8" 216' circulated with cement - 5 1/2" 3880' with 125 sax cement, limit
plug at 2850', set 4 sax cement at 2850', pulled 2800' 5 1/2" to 600', circulated
hole with heavy mud through 5 1/2" (30 sax Gal), displaced 20 sax cement through
5 1/2" at 600', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180',
heavy mud to 35', set bridge and filled with cement to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED

DATE 6/24/60

INV. NO. 1546-W